

WALL COPING INSTALLATION GUIDE



Skyline Line Coping



Using recommended fixing screws, fix wall coping strap to structure at maximum 1.5metre centres or as recommended based on wind uplift calculations. Note. water proofing membrane by others not shown.



Insure that a minimum 31mm gap is left on the overhang.



Skyline Line Coping



Locate wall coping over half of the wall bracket at joint and rotate down.



Apply pressure to the coping so as to clip the coping in place. Compressing the EPDM seal as shown. Repeat on the next length or fitting. Leave 4mm gap for expansion



Skyline Line Coping - indicative detail

